

Filterra® Installation Summary



1. Filterra units shipped with top slabs separated from boxes by wooden blocks. A set of lifting hooks provided.



2. A crane is used with a spreader bar or long slings to unload and set the units. Box is lifted separately from top slab.



3. Filterra boxes are set in pre-prepared holes with appropriate sub-grade per plan elevations.



4. Manufacturer-installed protective throat board and internal silt fabric are left in place to protect the unit from construction sediment. The top slab is set with butyl tape seal (also supplied).

For additional information please contact your local Filterra sales representative.
Eastern Zone: 866-349-3458, Western Zone: 877-345-1450.